BANGALORE DIVISION.

Abstract Notification dated 17th November 1938.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring and improving Kachanhalli Minor Tank, Reg. No. 88 of Nelamangala Taluk, published on pages 2091-2093, of Part VI of the *Mysore Gazette*, dated 24th November 1938.

2. The last date for the receipt of the tender is 2 P.M. on 12th December 1938. Duplicate challan for having credited the deposit amount of Rs. 260 into the treasury under "17 (*a*) P. W. Deposits" must accompany the tender.

Abstract Notification dated 28th November 1938.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring Dasenahalli Minor tank, Reg. No. 122 of Nelamangala Taluk, published in pages 2174—2177 of Part VI of the *Mysore Gazette*, dated 1st December 1938.

The last date for the receipt of the tender is 2 P.M. on 17th December 1938. Duplicate challan for having credited the deposit amount of Rs. 300 into the Treasury under "17 (*a*) P. W. Deposits" must accompany each tender.

Notice dated 6th December 1938.

TENDER NOTIFICATION FOR IMPROVING KATTIGENAHALLI TANK, REG. NO. 27 OF HOSKOTE TALUK.

The notice calling for tenders for the above work, *vide* pages 2172—2174, Part VI of the *Mysore Gazette*, dated 1st December 1938, is hereby withdrawn.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 21st November 1938.

The attention of the public is invited to the detailed notification dated 13th November 1938, published on pages 2122-2125, of Part VI of the *Mysore Gazette*, dated 24th November 1938, regarding the tenders for the construction of a Town Hall building at Malur, Kolar District.

The last date for receiving tenders is 12th December 1938 up to 12 NOON.

R. TIPPAIYA,
Executive Engineer.

MANDYA DIVISION.

Tender Notice dated 1st December 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 NOON on 17th December 1938, for constructing Maternity Home at Kyathanahalli, French-Rocks Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mandya Division, should be addressed to the Executive Engineer, Mandya Division, in a sealed cover and superscribed as "Tender for constructing Maternity Home at Kyathanahalli." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 290 (Rupees Two hundred and ninety only) in cash or treasury challan for this amount as earnest money. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest. After acceptance the successful tenderer will deposit an equal amount as security deposit.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 17th December 1938 at 12 noon. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mandya Division, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 10.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of February 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. .....which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide power and mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Provide his own machinary pipes, etc., for water supply and supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(5) It is the business of the contractor to make his own arrangements for quarries and supplies of materials

23. Only Mysore teak wood selected and purchased from Mysore Government Depot should be used.

24. Only Chamundi Cement should be used.

Abstract estimate for constructing a Maternity Home at Kyathanahalli French-Rocks Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation ..	C yd.	0 3 0	45	
2	Stone jelly concrete in lime mortar	C ft.	0 3 6	567	
3	Size stone in mud in foundation and basement including bond stones at every 6'	,,	0 3 3	1,085	
4	Burnt brick in mud in superstructure including scaffolding charges	,,	0 3 3	1,847	
5	Burnt brick in mortar for sides of doors and windows, etc.	,,	0 4 0	354	
6	R. C. C. bed slabs below girders	,,	1 2 0	4	
7	Providing burnt stone slabs 6" thick fixed in mortar and dressed all exposed faces ..	S.ft.	0 7 0	166	
8	Providing and fixing teakwood doors (Mysore teak) ½ panelled and ½ glazed (pin treaded glass) frames 3"×4" with brass parliamentary hinges and oxidised metal tower bolts and hooks complete (without bottom rail) ..	,,	1 12 0	32	
9	Teak wood doors, same as above fully panelled without bottom rail	,,	1 8 0	147.75	
10	Teak wood windows with fully glazed shutters (pin headed moroco glass) with brass parliamentary hinges, oxidised metal fittings with iron bars, etc.	,,	2 0 0	35	
11	Teak wood windows, with panelled shutters brass parliamentary hinges, oxidised metal fittings with iron bars, etc., complete (to be in 4 halves)	,,	1 12 0	140	
12	R. C. C. perforated ventilators	,,	1 0 0	4½	
13	Providing and fixing Tata's R. S. girders including hoisting)	Cwt.	14 0 0	10.8	
14	Encasing girders with initial coat of cement wash B. B. in lime mortar with wire, finished with lime plastering	L. S.	20 0 0	..	
15	Providing R. C. C. chajja over windows and in front verandah 2½'	S.ft.	0 10 0	164	
16	R. B. C. terrace, complete with 3" to 4" of brick kappe and top and bottom lime mortar plastering	Sqr.	55 0 0	14.87	
17	Cement pointing to basement	,,	3 0 0	2.33	
18	Lime mortar plastering 1" including rounding corners, etc.	,,	2 8 0	38.91	
19	Red colour dado (cement) in bath room	,,	10 0 0	2.33	
20	Flooring with 1½" jelly concrete cement mortar 1 : 4 on 4" jelly concrete in lime mortar and finishing with cement plastering ½" thick and red oxide including cutting into large squares, etc., complete	,,	20 0 0	11.60	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
21	Green colour painting to exposed portions of windows	Sqr.	3 0 0	1.40	
22	Varnishing the sides and faces of doors and windows	,,	2 8 0	4.83	
23	Size stone in lime mortar pillars with dressed stone base and capital complete with cement pointing.	No.	12 0 0	4	
24	Parapet wall including plastering and top moulding, etc., complete 1½′ to 2′	R.ft.	0 8 0	197	
25	C. I. rain water spouts or pipes or if zinc spouts of 4″ dia. are provided (a rate of Re. 0—5—6 per R.ft. to be allowed)	No.	6 0 0	10	
26	Miscellaneous charges such as perforated ventilators in parapet, etc.	L. S.	..	..	100 0 0
27	Whitewashing as per plastering	Sqr.	0 3 0	38	
28	Extra foundation during execution	L. S.	..	..	103 0 0
	Nurse's quarters.				
1	Earthwork excavation for foundation	C.yd.	0 3 0	14	
2	Stone jelly concrete in lime mortar	C.ft.	0 3 6	96	
3	Size stone in mud foundation and basement including bond stones at every 6′ apart	,,	0 3 3	375	
4	Burnt brick in mud superstructure	,,	0 3 3	860	
5	Burnt brick in mortar alround the doors and windows	,,	0 3 6	150	
6	Providing and fixing burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 7 0	67	
7	Providing and fixing teakwood door fully panelled with iron ninges without bottom rail	S.ft.	1 6 0	60	
8	Providing and fixing T. W. windows with panelled shutters, iron parliamentary hinges and iron bars each shutters to be 2 halves	,,	1 8 0	48	
9	R. C. C. perforated ventilators	,,	1 0 0	9	
10	Providing R. C. C. chejja over door	,,	0 10 0	12	
11	R. B. C. terrace complet with 3″ to 4″ brick kappe and top and bottom plastering	Sqr.	55 0 0	3.55	
12	Cement pointing to basement	,,	3 0 0	1.15	
13	Lime mortar plastering 1″ thick	,,	2 8 0	19.18	
14	Red colour dado	,,	10 0 0	0.40	
15	Cement plastering in kitchen and bath rooms	,,	7 0 0	1	
16	Flooring with 2″ jelly concrete in lime mortar 1½″ jelly concrete in cement mortar 1 : 4 and finishing with cement plastering including red-colouring and cutting into large squares	,,	20 0 0	1.53	
17	Flooring as above without red colour finish	,,	18 0 0	0.95	
18	Green colour painting to exposed portions of windows and doors	,,	3 0 0	0.69	
19	Varnishing inside faces of doors and windows	,,	2 8 0	1.05	
20	Parapet wall 1′ to 1½′ with plastering etc., complete	R.ft.	0 6 0	77	
21	Down water pipes (sponds)	No.	6 0 0	4	
22	Whitewashing 2 coats as per plastering	Sqr.	3 0 0	19	
23	Constructing :— Ovens, smoke escapes, shelf planks in kitchen and bath room, etc.	L. S.	..	..	24 0 0
	Constructing 2 Latrines.				
1	Earthwork excavating foundations	C.yd	0 3 0	3	
2	Stone jelly concrete in cement mortar 1 : 6	C.ft.	0 5 0	28	
3	Size stone in lime mortar, foundation	,,	0 3 9	59	
4	Burnt brick in mud	,,	0 3 3	67	
5	Burnt brick in mortar	,,	0 3 6	68	
6	Providing and fixing doors of zinc sheets without bottom or top rail including painting with chocolate and bolts complete	S.ft.	0 10 0	27	
7	Chunam plastering 1″ outside	Sqr.	2 8 0	2.06	
8	Cement plastering ½″ inside (1 : 2 : 4)	Sqr.	7 0 0	1.92	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs. a. p.
9	Flooring with 2" jelly concrete lime mortar 1½" jelly, concrete in cement mortar 1 : 4 and finishing with cement plastering	Sqr.	18 0 0	0.50	
10	Coping over walls	R.ft.	0 2 0	38	
11	Fixing outlet and constructing drain, etc. ..	L. S.	..	..	3 0 0
	Constructing Compound wall.				
1	Constructing burnt brick in mud compound wall as per sample excluding portion of Nurses' quarters, latrine and gate—complete with size stone in mud foundation and basement, finished with cement pointing to basement, lime mortar plastering to C. W. and coping as per design ..	R.ft.	1 6 0	437	
2	Providing and fixing wooden gate complete with iron work and bolts and green paint, etc., complete	„	3 0 0	12	
3	Extra for gate pillars such as cornice and capitals, etc.	L. S.	..	..	9 0 0
	Contingencies	L. S.	..	..	75 0 0
	Installation of electric lights	L. S.	..	..	264 0 0
	Well with water connection and drains	L. S.	..	..	200 0 0

M. V. KRISHNASWAMY IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 17th November 1938.

Attention of the public is hereby invited to the detailed notification dated the 16th November 1938, calling for the tenders for extending the Middle School at Kumsi, published in Part VI, pages 2125-2126, of the *Mysore Gazette*, dated the 24th November 1938.

The last date for receiving tenders is 3 P.M. on 10th December 1938.

M. K. RAJAM IYENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 2nd December 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 19th December 1938 for dismantling and reconstructing a bridge in 7/169 of Salem-Ballary Road.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for dismantling and reconstructing a bridge in 7/169 of Salem-Bellary Road." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 300 (in words) rupees three hundred in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers as wish to be present on or about 24th December 1938, at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.